



- NOTES**
1. DO NOT SCALE FROM DRAWINGS, USE GIVEN DIMENSIONS ONLY.
 2. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
 3. BACKFILL MATERIAL TO GABIONS TO BE CLASS 6N/GP (Ø<-387) IN ACCORDANCE WITH THE D800 SPECIFICATION APPENDICES.
 4. GABION FILL SHALL BE SELECTED GRANULAR MATERIAL CLASS 6N IN ACCORDANCE WITH THE D800 SPECIFICATION APPENDICES. THE FILL SHALL BE FREE DRAINING AND DURABLE STONE SUCH AS QUARRIED OR NATURALLY OCCURRING ROUNDED STONE.
 5. FOUNDING LEVEL TO FOLLOW SLOPE OF THE ROAD. FORMATION LEVEL TO BE INSPECTED PRIOR TO COMMENCING GABION WALL CONSTRUCTION.
 6. ANY SOFT SPOTS DETECTED PRIOR TO OR DURING PARTITIONS OPERATIONS TO BE EXCAVATED AND BACKFILLED WITH ACCEPTABLE FILL MATERIALS OF SIMILAR CHARACTERISTICS TO THE SURROUNDING MATERIALS. CLASS 6A MATERIAL TO BE ADOPTED IF BACKFILL BELOW GROUNDWATER LEVEL. SOFT MATERIAL IS DEFINED AS HAVING AN UNDRAINED SHEAR STRENGTH LESS THAN 50kN/m² WHEN MEASURED BY HAND VANE OR SIMILAR.
 7. GABION WALL TO BE CONSTRUCTED WITH 6 DEGREE BATTER FROM VERGE (NOT SHOWN).
 8. CONSTRUCTION OF GABION WALL IS MEASURED BACK FROM THE NEW WINGWALL FACE.
 9. THE ESTIMATED THICKNESS OF TOPSOIL AND WADHURST CLAY FORMATION IS ~1.20m WITH TOPSOIL PROVEN TO A THICKNESS OF 0.32m IN PLACES.
 10. TO MITIGATE THE RISK OF FAILURE DUE TO THE PRESENCE OF RELIC SHEAR SURFACES IN THE WADHURST CLAY FORMATION, RELIC SHEAR SURFACES SHALL BE EXCAVATED AND RECOMPACTED DURING CONSTRUCTION BETWEEN CH. 355 AND CH. 400.
 11. RELIC SHEAR SURFACES IN THE WADHURST CLAY STRATUM TO BE EXCAVATED AND REPLACED WITH ADEQUATE FILL FOR EMBANKMENT CONSTRUCTION BETWEEN CH. 345 AND CH. 355.
 12. FOR DETAILS OF PAVEMENT REFER TO SERIES 0700 DRAWINGS.
 13. FOR DETAILS OF UTILITIES REFER TO SERIES 2700 DRAWINGS.
 14. FINISHED SLOPE TO BE VEGETATED. FOR DETAILS OF VEGETATION REFER TO SERIES 3000 DRAWINGS.



CROSS SECTION
 (CHAINAGE 380)
 SCALE 1:50



DETAIL 'D'
 SCALE 1:25

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION	
In addition to the instructions provided, read the type of work detailed on this drawing, note the following:	
CONSTRUCTION	PRESENCE OF RELIC SHEAR SURFACES TO A DEPTH OF 0.5m FROM THE TOP OF THE WADHURST CLAY STRATUM. FINAL DEPTH OF EXCAVATION TO BE CONFIRMED ON SITE.
MAINTENANCE / CLEANING	
DECOMMISSIONING / DEMOLITION	

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement.

NO.	STATUS	FOR INFORMATION	CH.	SO.	SO.	AP.
Rev	Rev	Date	Dimension	Checked	Drawn	Approved

JACOBS
 Simpson House, 6 Cherry Orchard Road, Coppin, Surrey, CH9 6BE
 Tel: +44(0)208 886 8212 Fax: +44(0)208 881 2489
 www.jacobs.com

MOCHTIE TRaylor
 4th Floor, 100, Market Street, Manchester, M1 2HT
 www.mochtietraylor.com

Client: **Greenway**
 Employer: **Greenway**

Project: **BEXHILL TO HASTINGS LINK ROAD**

Drawing title: **Greenwat around Decoy Pond Wood Ch. 4700 Gabion Wall - Greenway Ch. 380m**

Drawing status: **ISSUED FOR REVIEW**

Scale: **AS SHOWN @ A1 DO NOT SCALE**

Jacobs No.: **B1297000-PH2**

Client No.: **AS SHOWN @ A1**

Drawing number: **B1297000-PH2/0600.01a/0213**

Rev: **R0**

Reproduction from the Ordnance Survey Map with the permission of the controller of Her Majesty's stationery office Crown copyright reserved Licence No. AL 100017326