

Drawing number / Rev  
B1297000-PH2/3000.01a/0010 C4



- NOTES**
- All dimensions in metres unless otherwise stated.
  - For complete fencing key, refer to fencing drawings.
- KEY**
- High Forest - Dry (Planting at 2m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
  - High Forest - Dry (Planting at 2.6m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
  - High Forest - Wet (Planting at 2m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
  - High Forest - Wet (Planting at 2.6m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
  - Dry Woodland Edge (3m wide, planting at approximately 1.2 - 1.5m centres in three staggered rows, random mix of 3-5 species (LE2.1 and LE2.4.1) Care must be taken not to plant in obvious or straight lines. Refer to plant spacing detail on drawing B1297000/3000.01a/0001
  - Wet Woodland Edge (3m wide, planting at approximately 1.2 - 1.5m centres in three staggered rows, random mix of 3-5 species (LE2.1 and LE2.4.1) Care must be taken not to plant in obvious or straight lines. Refer to plant spacing detail on drawing B1297000/3000.01a/0001
  - Scrub random mix in groups of 3 - 5 of each species (LE2.8)
  - Wetland Scrub random mix in groups of 3 - 5 of each species (LE2.8)
  - Existing Woodland to be managed (LE2.1.1)
  - Existing Woodland Edge to be Managed (LE2.2)
  - Scattered Trees in Wet Grassland, Marsh and Fen (LE4.1.1) Refer to plant spacing detail on drawing B1297000/3000.01a/0001
  - Scattered Scrub in Neutral Grassland (LE6.1.3.1) Refer to plant spacing detail on drawing B1297000/3000.01a/0001
  - Climbing plants on fences and structures - 4m linear spacing unless otherwise noted.
  - Woodland/woodland edge in-fill planting
  - Amenity Trees and Shrub Planting (LE3.1)
  - Extra heavy standard, semi-mature tree or multi-stem tree
  - Site of Special Scientific Interest (SSSI)
  - Site of Nature Conservation Importance (SNCI)
  - Native Species Hedgerows (LE4.3) Two staggered rows, planted at 0.5m centres, 0.5m between rows
  - Native Hedgerows with Trees (LE4.4) Two staggered rows, planted at 0.5m centres, 0.5m between rows. Trees shall be planted between rows at an average of 10m - 15m centres. Each tree shall be marked/identified with a pole as described in Appendix 3.0 & 3.1 planting. Setting out sub-section VII in Revision 9 (or later) of the Series 3000 Appendices.
  - Ditch
  - Watercourse
  - Pond
  - Public Footpath
  - Byway
  - Bridleway
  - Existing trees, hedges & scrub to be retained
  - Woodland management zones
  - CPQ boundary
  - BF - BF - Ball fence
  - CB - CB - 1.8m close boarded fence
  - EP - EP - Post and wire fence with badger proofing
  - F&R - Timber post and four rail fence
  - ABNB - 1.8m high absorptive noise barrier
  - REH1 - 1.8 & 1.5m high reflective noise barriers
  - E - Existing fence

C4	18/12/2015	Minor Planting Changes	LC	AS	AS	PDF
C3	04/11/2015	Planting revs to match scheme changes	AS	RM	RM	PDF
C2	11/08/2015	Plant Schedule Updated to Match Changes	CC	AS	TD	JP
C1	02/03/2015	Rev to match minor scheme layout changes	RM	AS	AB	JP
C0	26/07/2014	ISSUE FOR CONSTRUCTION	AS	RM	RM	AS
Rev	Rev. Date	Purpose of revision	Drawn	Checked	Rev'd	Apprv'd

**JACOBS**  
Simpson House, 6 Cherry Orchard Road, Croydon, Surrey, CR9 5BE  
Tel: +44(0)208 666 8212 Fax: +44(0)208 681 2499  
www.jacobs.com

Client: HOCHTIEF  
Employer: TAYLOR WOODROW

Project: BEXHILL TO HASTINGS LINK ROAD

Drawing title: PLANTING SHEET 10 OF 14

Drawing status: FOR CONSTRUCTION

Scale: 1:1000 @ A1 DO NOT SCALE

Jacobs No. B1297000

Client no.

Drawing number: B1297000-PH2/3000.01a/0010 Rev C4

**SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION**

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:

**CONSTRUCTION**

- Likelihood of fly-tipped hazardous substances
- Existing overhead and underground high voltage cables
- Working near overhead power lines at dormouse crossing point
- Working adjacent to a railway
- Working on slopes steeper than 1:3
- Working near to site plant and other machinery

**MAINTENANCE / CLEANING**

Same as for construction

**DECOMMISSIONING / DEMOLITION**

Same as for construction

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement

Reproduction from the Ordnance Survey Map with the permission of the controller of Her Majesty's Stationery Office Crown copyright reserved Licence No. AL 100017329