

NOTES
 1. All dimensions in metres unless otherwise stated.

KEY

- High Forest - Dry (Planting at 2m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
- High Forest - Wet (Planting at 2.5m centres, random mix in groups of 3-5 of each species) (LE2.1 and LE2.4.1)
- Dry Woodland Edge (3m wide, planting at approximately 1.2 - 1.5m centres in three staggered rows, random mix of 3-5 species (LE2.1 and LE2.4.1) Care must be taken not to plant in obvious or straight lines. Refer to planting spacing detail on drawing B1297000/3000.01a/0001)
- Wet Woodland Edge (3m wide, planting at approximately 1.2 - 1.5m centres in three staggered rows, random mix of 3-5 species (LE2.1 and LE2.4.1) Care must be taken not to plant in obvious or straight lines. Refer to planting spacing detail on drawing B1297000/3000.01a/0001)
- Scrub random mix in groups of 3 - 5 of each species (LE2.8)
- Existing Woodland to be managed (LE2.1.1)
- Existing Woodland Edge to be Managed (LE2.2)
- Scattered Trees in Wet Grassland, Marsh and Fen (LE6.4.1.1) Refer to planting spacing detail on drawing B1297000/3000.01a/0001
- Scattered Scrub in Neutral Grassland (LE6.1.3.1) Refer to planting spacing detail on drawing B1297000/3000.01a/0001
- Amenity Tree and Shrub Planting (LE3.1)
- Site of Special Scientific Interest (SSSI)
- Site of Nature Conservation Importance (SNCI)
- Native Species Hedgerow (LE4.3) Two staggered rows, planted at 0.5m centres, 0.5m between rows
- Native Hedgerows with Trees (LE4.4) Two staggered rows, planted at 0.5m centres, 0.5m between rows. Trees shall be planted between rows at an average of 10m - 15m centres
- Ditch
- Watercourse
- Pond
- Public Footpath
- Byway
- Bridleway
- Existing trees, hedges & scrub to be retained

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION


In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:

CONSTRUCTION
 Likelihood of fly-tipped hazardous substances
 Existing overhead and underground high voltage cables
 Working adjacent to a railway
 Working on slopes steeper than 1:3
 Working near to site plant and other machinery

MAINTENANCE / CLEANING
 Same as for construction

DECOMMISSIONING / DEMOLITION
 Same as for construction

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement



| Rev | Rev. Date | Purpose of revision | Drawn | Checked | Rev'd | Apprv'd |
|-----|------------|---------------------------------|-------|---------|-------|---------|
| R3 | 09/01/2013 | PONDS + CPO BOUNDARY ADDED | RM | AS | AS | AB |
| R2 | 13/12/2012 | ISSUED FOR REVIEW | DH | AS | AS | AB |
| R1 | 07/11/2012 | CONTOURS & EXISTING TREES ADDED | AC | AS | AS | AB |
| R0 | 12/10/2012 | INITIAL ISSUE | RM | ES | AS | AB |

JACOBS
 Simpson House, 6 Cherry Orchard Road, Croxson, Surrey, CR9 6BE
 Tel: +44(0)208 666 8212 Fax: +44(0) 208 681 2499
 www.jacobs.com

Client: **HOCHTIEF** Employer: **East Sussex Water**

Project: **BEXHILL TO HASTINGS LINK ROAD**

Drawing title: **PLANTING SHEET 8 OF 14**

Drawing status: **ISSUE FOR REVIEW**

Scale: 1:1000 @ A1 **DO NOT SCALE**

Jacobs no. B1297000

Client no. **B1297000-PH2/3000.01a/0008 R3**

Reproduction from the Ordnance Survey Map with the permission of the controller of Her Majesty's Stationery Office. Crown copyright reserved. Licence No. AL 10017326

FOR CONTINUATION, SEE DRAWING NO. 0013

FOR CONTINUATION, SEE DRAWING NO. 0009

P:\B1297000\B1297000 Bexhill Hastings\Phase 2 - Detailed Design\600 CAD\603 Drawings\3000 Landscape & Ecology